

GENERAL NOTES – INSIDE CITY LIMITS

1. Construct wastewater collection systems, water lines, storm drainage and street paving in accordance with the latest edition of the publications Standard Construction Specifications For Wastewater Collection Systems, Water Lines, Storm Drainage, Street Paving, and Standard Construction Details For Wastewater Collection Systems. Water Lines, Storm Drainage, and Street Paving published by the City of Houston, Department of Public Works and Engineering.
2. The geotechnical investigation for this project was conducted in accordance with Chapter 11 of the latest edition of the publication Infrastructure Design Manual, published by the City of Houston, Department of the Public Works and Engineering. Soils report was prepared by [Geotechnical Engineering Firm] Report No. [No. of Report], dated [Date of Report].
3. Utilities presented on these drawings are shown based on the best available information. Contractor shall verify the exact locations in the field prior to commencing construction. Contractor shall notify Texas One Call at 713-223-4567/800-245-4545 and Lone Star One Call at 800-669-8344 at least 48 hours before proceeding with any excavation.
4. Contractor shall be responsible for damages to existing water, wastewater, storm water lines and traffic control devices. Damages shall be repaired in accordance with the City of Houston, Department of Public Works and Engineering's Standard Construction Specifications for Wastewater Collection System. Water Lines, Storm Drainage, and Street Paving and Standard Construction Details for Wastewater Collection Systems, Water Lines, Storm Drainage, and Street Paving, referenced above, at no additional cost.
5. Contractor shall notify the office of the City Engineer, Department of Public Works and Engineering via fax at 832-395-4424 (fax) for inspection at least 48 hours prior to commencing construction.
6. Adequate drainage shall be maintained at all time during construction and any drainage ditch or structure disturbed during construction shall be restored to existing conditions or better.
7. Contractor shall take necessary precautions to protect root systems of shrubs, plants and trees along the area of excavation.
8. Contractor shall comply with latest edition of OSHA regulations and the State of Texas laws concerning excavation.
9. Contractor shall maintain a set of redline drawings recording as-built conditions during construction. These redline marked up drawings will be submitted to the Design Consultant who will make the changes on the original tracings, labeling each sheet in the set as "Record Drawings", and returning same to the City Engineer.