

Section 01575

STABILIZED CONSTRUCTION EXIT

PART 1 G E N E R A L

1.01 SECTION INCLUDES

- A. Installation of erosion and sediment control for stabilized construction exits used during construction and prior to final development of site.

1.02 MEASUREMENT AND PAYMENT

- A. Unit Price Contracts. If Contract is Unit Price Contract, payment for work in this Section will be based on the following:
  - 1. Stabilized construction roads, parking areas, exits and truck-washing areas: per square yard of aggregate placed in 8-inch layers. No separate payment will be made for street cleaning necessary to meet TPDES requirements. Include cost of work for street cleaning under related Specification section.
- B. Stipulated Price (Lump Sum) Contracts. If the Contract is a Stipulated Price Contract, include payment for work under this Section in the total Stipulated Price.

1.03 SUBMITTALS

- A. Conform to requirements of Section 01330 - Submittal Procedures.
- B. Submit manufacturer's catalog sheets and other Product Data on geotextile fabric.
- C. Submit sieve analysis of aggregates conforming to requirements of this Specification.

1.04 REFERENCES

- A. ASTM D 4632 - Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.
- B. Storm Water Quality Management Guidance Manual prepared by the City of Houston, Harris County and Harris County Flood Control District.

PART 2 P R O D U C T S

2.01 GEOTEXTILE FABRIC

- A. Provide woven or non-woven geotextile fabric made of polypropylene, polyethylene, ethylene, or polyamide material.
- B. Geotextile fabric: Minimum grab strength of 270 psi in any principal direction (ASTM D-4632) and equivalent opening size between 50 and 140.
- C. Geotextile and threads: Resistant to chemical attack, mildew, and rot and contain ultraviolet ray inhibitors and stabilizers to provide minimum of six months of expected usable life at temperature range of 0 to 120 degrees F.
- D. Representative Manufacturers: Mirafi, Inc. or equal.

2.02 COARSE AGGREGATES

- A. Coarse aggregate: Crushed stone, gravel, crushed blast furnace slag, or combination of these materials. Aggregate shall be composed of clean, hard, durable materials free from adherent coatings of, salt, alkali, dirt, clay, loam, shale, soft or flaky materials, or organic and injurious matter.
- B. Coarse aggregates shall conform to following gradation requirements.

<u>Sieve Size</u> <u>(Square Mesh)</u>	<u>Percent Retained</u> <u>(By Weight)</u>
2-1/2"	0
2"	0 - 20
1-1/2"	15 - 50
3/4"	60 - 80
No. 4	95 - 100

PART 3 E X E C U T I O N

3.01 PREPARATION AND INSTALLATION

- A. Provide stabilized construction roads and exits at construction, staging, parking, storage, and disposal areas to keep street clean of mud carried by

construction vehicles and equipment. Construct erosion and sediment controls in accordance with Drawings and Specification requirements.

- B. Do not clear grub or rough cut until erosion and sediment control systems are in place, unless approved by Project Manager to allow soil testing and surveying.
- C. Maintain existing construction site erosion and sediment control systems until acceptance of the Work or until removal of existing systems is approved by Project Manager.
- D. Regularly inspect, repair or replace components of stabilized construction exits. Unless otherwise directed, maintain stabilized construction roads and exits until the City accepts the Work. Remove stabilized construction roads and exits promptly when directed by Project Manager. Discard removed materials off-site.
- E. Remove and dispose of sediment deposits at designated spoil site for Project. If a spoil site is not designated on Drawings, dispose of sediment off-site at a location not in or adjacent to stream or flood plain. Assume responsibility for off-site disposal.
- F. Spread compacted and stabilized sediment evenly throughout site. Do not allow sediment to flush into streams or drainage ways. Dispose of contaminated sediment in accordance with existing federal, state, and local rules and regulations.
- G. Prohibit equipment and vehicles from maneuvering on areas outside of dedicated rights-of-way and easements for construction. Immediately repair damage to erosion and sediment control systems caused by construction traffic.
- H. Conduct construction operations in conformance with erosion control requirements of Specification 01570 – Storm Water Pollution Control.

### 3.02 CONSTRUCTION METHODS

- A. Provide stabilized access roads, subdivision roads, parking areas, and other on-site vehicle transportation routes where shown on Drawings.
- B. Provide stabilized construction exits and truck washing areas, when approved by Project Manager, of sizes and at locations shown on Drawings or as specified in this Section.
- C. Clean tires to remove sediment on vehicles leaving construction areas prior to entering public right-of-ways. Construct truck washing areas needed to

remove sediment. Wash trucks on stabilized areas that drain into drainage systems protected by erosion and sediment control measures.

- D. Details for stabilized construction exits are shown on Drawings. Construct other stabilized areas to same requirements. Maintain minimum roadway widths of 14 feet for one-way traffic and 20 feet for two-way traffic and of sufficient width to allow ingress and egress. Place geotextile fabric as a permeable separator to prevent mixing of coarse aggregate with underlying soil. Limit exposure of geotextile fabric to elements between laydown and cover to a maximum 14 days to minimize potential damage.
- E. Grade roads and parking areas to provide sufficient drainage away from stabilized areas. Use sandbags, gravel, boards, or similar materials to prevent sediment from entering public right-of-ways, receiving streams or storm water conveyance systems.
- F. Inspect and maintain stabilized areas daily. Provide periodic top dressing with additional coarse aggregates to maintain required depth. Repair and clean out damaged control systems used to trap sediment. Immediately remove spilled, dropped, washed, or tracked sediment from public right-of-ways.
- G. Maintain lengths of stabilized areas as shown on Drawings or a minimum of 50 feet. Maintain a minimum thickness of 8 inches. Maintain minimum widths at all points of ingress or egress.
- H. Stabilize other areas with the same thickness, and width of coarse aggregate required for stabilized construction exits, except where shown otherwise on Drawings.
- I. Stabilized areas may be widened or lengthened to accommodate truck washing areas when authorized by Project Manager.
- J. Clean street daily before end of workday. When excess sediments have tracked onto streets, Project Manager may direct Contractor to clean street as often as necessary. Remove and legally dispose of sediments.
- K. Use other erosion and sediment control measures to prevent sediment runoff during rain periods and non-working hours and when storm discharges are expected.

END OF SECTION